APDCL SCHEDULE OF ITEMS TENDER NOTICE :1 OF 2024-25

Name of work: Construction of new LT overhead feeder with aerial bunched cable for the

service connection at	Arts and (Commerce De	partment of D.U.

SL No	Description Description	Qty./Unit	Rate in figures Words / Each	Amount in Rupees
1	Supplying and erection G.I. Tubular pole 8.5 mtrs including pole grouting with PCC work.	9Nos		
2	Supplying and fitting LT stay set including grouting with PCC work.	8Nos		
3	Supplying and fitting of hot dipped G.I. stay wire 7/14SWG.	40Kg		
4	Supplying and erection 3Cx120+1Cx95 Sqmm (Messenger Cum Neutral) + 1C 25Sqmm for Street lighting.	535Mtrs		
5	Supplying and fitting Suspension clamp ABC as per NFC Standard.	24Nos		

6	Supplying and fitting Insulating Piercing connector IPC P ² x95 for ABC to ABC Tee Connection as per NFC Standard.	2Nos
7	Supplying and fitting Anchor clamp wedge type LT AB as per NFC Standard.	6Nos
8	Supplying and fitting Cable end cap for ABC cable.	8Nos
9	Supplying and fitting Pole Clamp G.I. Flat 50mmx6mm.	36Nos
10	Supplying fitting Eye Hook for Anchor and suspension clamp.	18Nos

11	Supplying fitting G.I. Nut and Bolt (Assoprted)	27Kg
12	Supplying fitting L.T. Guy Insulator (Porcelain)	8Nos
13	Supplying of Sundry materials L/S.	1No
	Rates should be inclusive of all taxes.	

Rates should be inclusive of all taxes.	
Date	Signature of Tenderer with seal
Date	Signature of Tenderer with sear
	Contractor Name:
	Address:
	Reg. No.:

APDCL SCHEDULE OF ITEMS TENDER NOTICE :1 OF 2024-25

Name of work: Construction of new LT overhead feeder with aerial bunched cable for the service connection at Pharmaceutical Science Department, Petroleum Technology Department, Applied Geology Department and Education

Department of D.U.

-	Department of D.U.	04. 11114	Rate in figures Words /	Amount in Rupees
SL No	Description	Qty./Unit	Each	Amount in Naposo
1	Supplying and erection G.I. Tubular pole 8.5 mtrs including pole grouting with PCC work.	15Nos		
2	Supplying and fitting LT stay set including grouting with PCC work.	16Nos		
3	Supplying and fitting of hot dipped G.I. stay wire 7/14SWG.	80Kg		
4	Supplying and erection 3Cx120+1Cx95 Sqmm (Messenger Cum Neutral) + 1C 25Sqmm for Street lighting.	498Mtrs		
5	Supplying and fitting Suspension clamp ABC as per NFC Standard.	23Nos		

6	Supplying and fitting Insulating Piercing connector IPC P ² x95 for ABC to ABC Tee Connection as per NFC Standard.	4Nos	
7	Supplying and fitting Anchor clamp wedge type LT AB as per NFC Standard.	6Nos	
8	Supplying and fitting Cable end cap for ABC cable.	8Nos	
9	Supplying and fitting Pole Clamp G.I. Flat 50mmx6mm.	46Nos	
10	Supplying fitting Eye Hook for Anchor and suspension clamp.	23Nos	

11	Supplying fitting G.I. Nut and Bolt (Assoprted)	35Kg	
12	Supplying fitting L.T. Guy Insulator (Porcelain)	16Nos	
13	Supplying of Sundry materials L/S.	1No	
14	Supplying and fitting IPC for 50-70 Sqmm both main and service cable for connecting DB Box.	4Nos	
15	Supplying and fitting Buckle for steel strap for DB fixing.	8Nos	

16	Supplying and fitting ASA Distribution box with pre-fitted lug for 250A 3 Phase 10 connector with spring service connection.	4Nos	
17	Supplying and fitting Steel strap for insulating DB size 20mmx1mm long.	8Nos	
	Rates should be inclusive of all taxes.		

Date

Signature of Tenderer with seal

Contractor Name:

Address:

Reg. No.:

Space to be used for Bank's Pad

SOLVENCY CERTIFICATE

This is to certify that Mr./Mrs./M/s
This certificate is issued on the express understanding that neither the bank nor any of its officials undertake any liability in respect thereof.
This certificate is issued at the specific request of Mr./Mrs./M/s.
Branch Manager
(Signature with seal)